Item No	Description
17	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregares of ready mixef concrete for RCC works laid in 15 cms thick layers and well compated including vibrating, curing,etc., with all lead and lifts etc complete(excluisive of cost of steel and fabrication charges) Ready Mixed Cement Concrete for Beams, Staircase and Roof with M-25 Roof Beams
19	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specification.
20	Providing and removing Centering, shuttering, strutting, propping etc.,and removal of from work for vertical surface such as walls at any thickness including attched plasters, butresses, plinth cills and string courses cost of all materials, labour complete as per specification
21	Providing and removing cenering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications
22	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintles exceeding 1 m in depth incluidng cost of all materials, labour complete as per specifications.
23	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials labour complete as per specificaiton. Staircase.
33	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.TMT Bars Fe 500.
	Total Cost(Rs)

CERTIFICATE:

1) Certified that the above work Carried out as per Specifications and work done satisfactorily

2) Certified that the above Work Execavated earth and debries cleared from the work spot.

Assistant Engineer(P)
Rajarajeswarinagara

Assistant Executive Engineer (P)
Rajarajeswarinagara Zone

unit	Previous		Present Measurement			Total Up-today	
	Qty	Cost			Cost	Qty	Cost
CUM	0.00	0.00	27.17	7300.00	198341.00	27.17	198341.00
CUM	0.00	0.00	81.85	6000.00	491100.00	81.85	491100.00
SQM	0.00	0.00	258.37	375.00	96889.00	258.37	96889.00
SQM	0.00	0.00	612.41	600.00	367443.00	612.41	367443.00
SQM	0.00	0.00	285.96	500.00	142982.00	285.96	142982.00
SQM	0.00	0.00	27.92	500.00	13960.00	27.92	13960.00
TONNE	0.00	0.00	25.30	75000.00	1897500.00	25.30	1897500.00
					6144199.00		**6144199.00**